



ABBREVIATIONS

AGC	AGGREGATE BASE COURSE
APPROX.	APPROXIMATE/APPROXIMATELY
CL, C/L	CENTER LINE
CO, C.O.	CLEANOUT
CONC	CONCRETE
DIA	DIAMETER
DI	DROP INLET
EL., ELEV	ELEVATION
ETC.	ET CETERA
EX., EXIST.	EXISTING
INV	INVERT
LBS	POUNDS
MAX	MAXIMUM
MIN	MINIMUM
N	NORTHING
NCSC	NORTH CAROLINA EROSION AND SEDIMENT CONTROL
NCDOT	NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
O.C.	ON CENTER
O.D.	OUTSIDE DIAMETER
PE	POLYETHYLENE
PVC	POLYVINYLCHLORIDE (PIPE)
RCP	REINFORCED CONCRETE PIPE
SMH	SANITARY SEWER MANHOLE
SVC	SERVICE
TBM	TEMPORARY BENCHMARK
TYP	TYPICAL
W/	WITH
&	AND
+	PLUS OR MINUS
%	PERCENT

CIVIL LEGEND

EXISTING	DESCRIPTION	NEW
	WATER VALVE	
	POST INDICATOR VALVE	
	THRUST BLOCK	
	FIRE HYDRANT	
	FIRE DEPT CONNECTION	
	SANITARY SEWER MANHOLE	
	SANITARY SEWER MANHOLE	
	STORM SEWER MANHOLE	
	STORM SEWER MANHOLE	
	STEAM MANHOLE	
	STORM DRAIN	
	PEDESTAL	
	LIGHT POLE	
	GUY WIRE	
	SANITARY SEWER (GRAVITY)	
	STORM SEWER	
	DOMESTIC WATER	
	FIRE WATER	
	OVERHEAD ELECTRICAL	
	UNDERGROUND ELECTRICAL	
	UNDERGROUND GAS	
	UNDERGROUND COMMUNICATIONS	
	CHILLED WATER SUPPLY & RETURN	
	CONCRETE	
	ASPHALT	
	TEMPORARY BENCHMARK	
	SPOT ELEVATIONS	+5.00
	CONTOUR LINES	-5.00
	TREE	
	SILT FENCE	
	SURVEY CONTROL POINT	
	SOURCE/DESTINATION UNKNOWN	
	DEMOLITION	

GENERAL CONSTRUCTION NOTES:

1. THE LOCATION AND DEPTHS OF EXISTING UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SCANNING THE AREA OF WORK TO HIS OWN SATISFACTION THE EXTENT OF UTILITIES PRESENT INCLUDING THE UTILITIES IDENTIFIED TO BE PRESENT, THOSE NOT SHOWN, AND THOSE SHOWN TO BE IN A DIFFERENT LOCATION.
2. THE WORK SITE FEATURES OUTSIDE THE AREA OF WORK OR THOSE FEATURES NOT RELEVANT TO THE WORK BEING PERFORMED ARE NOT SHOWN FOR CLARITY.
3. GRADE EVENLY BETWEEN SPOT ELEVATIONS SHOWN.

GENERAL REQUIREMENTS

1. ALL DISTURBED AREA SHALL BE VEGETATED IN ACCORDANCE WITH THE PROJECT VEGETATION PLAN. SEE DETAIL C3, SHEET CC501.

DEMOLITION WORK ITEMS:

- 1 EXISTING ASPHALT TO BE REMOVED. SEE SPECIAL SCHEDULING REQUIREMENTS.
- 2 EXISTING CONCRETE SIDEWALK TO BE REMOVED.
- 3 EXISTING LIGHT POLE & UNDERGROUND ELECTRIC SERVICE TO BE RELOCATED. SEE SITE ELECTRIC PLANS.
- 4 EXISTING TREE TO BE REMOVED.
- 5 EXISTING ROOF DOWNSPOUT TO BE REMOVED.
- 6 EXISTING GATE TO BE REMOVED.
- 7 EXISTING SIGNS TO BE REMOVED.
- 8 EXISTING HAZMAT STORAGE SHED TO BE RELOCATED. SEE SHEET CS101 FOR NEW LOCATION.

SPECIAL SCHEDULING REQUIREMENTS:

THE NEW EXTERIOR DRIVEWAY PAD LOCATED ON THE SOUTHEASTERN SIDE OF THE EXISTING CLINIC SHALL BE COMPLETED AND READY FOR OPERATION AS APPROVED BY CONTRACTING OFFICER BEFORE WORK IS STARTED ON REMOVAL OF THE WESTERN SIDE OF THE DRIVEWAY LOOP. THE INTENT IS TO MAINTAIN CONTINUOUS UNINTERRUPTED VEHICULAR ACCESS TO THE EXISTING REAR DOOR BENEATH THE PORTE-COCHERE THROUGHOUT CONSTRUCTION FOR DROP OFF AND PICK UP OF HANDICAPPED PATIENTS, AS WELL AS FOR EMERGENCY VEHICLE ACCESS.

JAЕ PROJECT # 11021

AVOLIS ENGINEERING, P.A.
 P.O. BOX 15564
 NEW BERN, NC 28561
 PH (252) 633-0068, FAX (252) 633-6507

PHYSICAL AND TOPOGRAPHIC SURVEY BY:
 Atlantic Survey & Design, P.A.
 1305 Country Club Road
 New Bern, North Carolina
 (252) 633-6649 JOB #31031

SCALE: AS NOTED
 EPROJECT NO. 1132806
 CONSTR. DRAWING NO.
 NAUFAC DRAWING NO. 12805605
 SHEET 6 OF 74

CD101

APPROVED: [Signature]

FOR COMMANDER NAUFAC

ACTIVITY

SATISFACTORY TO: DATE

DES: JKA | DWR: WWF | CHK: JKA

BRANCH MANAGER: [Signature]

CHIEF ENG/ARCH: [Signature]

NAVAL FACILITIES ENGINEERING COMMAND ~ MID-ATLANTIC

MARINE CORPS BASE CAMP LEJEUNE, NC

MARSOC COMPLEX - BUILDING RR440

HM2 CHARLES "LUKE" MILAM AID STATION

EXISTING CONDITIONS AND DEMOLITION

DATE: [Blank]

DESCRIPTION: [Blank]

SYN: [Blank]

APP: [Blank]

NAUFAC DRAWING NO. 12805605

SHEET 6 OF 74

CD101

REVISIONS: [Blank]

FILE NAME: P:\11021_MILAM CLINIC EXPANSION\11021_FINAL.DWG LAYOUT NAME: CD101 (Ex. Cond & Demo) PLOT DATE: Thursday, September 22, 2011 1:19:00pm