

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE 1 OF 2 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0003		3. EFFECTIVE DATE 7-5-11	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 110065
6. ISSUED BY CODE bab Officer in Charge of Construction MCI-East 1005 Michael Road Camp Lejeune, NC 28547-2521		7. ADMINISTERED BY (If other than Item 6) CODE See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-11-R-0065
			X	9B. DATED (SEE ITEM 11) 6-09-11
				10A. MODIFICATION OF CONTRACT/ORDER NO.
				10B. DATED (SEE ITEM 11)
CODE	FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended.
 Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

Project 110065, Demolish Buildings M501, M503, 106 and 909

SEE CONTINUATION SHEET

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	
15C. DATE SIGNED		16C. DATE SIGNED	
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

CONTINUATION SHEET

Most of the questions below are related to General Note 1 on Sheet T1. CONTRACTOR SHALL REMOVE ALL ITEMS SHOWN AND/OR NOTED ON THE DRAWINGS UNLESS INDICATED OTHERWISE. If the item is shown and/or noted on the plan it is to be removed. If the item is shown on the drawing and noted to remain, it stays in place.

The answers to the questions are below in all caps.

A6:

1.) Are the drop inlets on either end of the building being removed, and the lines leading to them off the main that is being removed

RESPONSE: SEE NOTE IN EMAIL ABOVE.

2.) There is an underground steam line that needs to be removed that seems to go under a curb and gutter, remove and replace curb and gutter?

RESPONSE: THE BUILDING 909 SITE HAS NO CURB AND GUTTER.

3.) The majority of the underground lines being removed are under asphalt, do I need to include a price for saw cutting strips of the asphalt to access the lines for removal?

RESPONSE: YES SAW CUT THE ASPHALT TO REMOVE THE LINES BELOW. IN CONVERSATIONS WITH THE BASE IT HAS BEEN DETERMINED THAT ASPHALT PAVING SHALL BE PROVIDED TO PATCH REMOVED STRIPS OF EXISTING ASPHALT.

A4:

1.) There is an underground electrical line running from a transformer to the left of the building. Is the transformer being removed along with the underground electrical line from the transformer to the building?

RESPONSE: THE TRANSFORMER IN THE YARD OF BUILDING 106 IS SHOWN TO BE REMOVED ON THE DRAWINGS. THE TRANSFORMER NEAR BUILDING 102 SHALL REMAIN.

2.) There are two 24" trees located to the right of the building, are these to be removed?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

3.) Is the asphalt parking lot in the front of the building being removed?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

4.) Is the concrete slab in the back of the building being removed?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

5.) In relation to the asphalt parking lot, it says to saw cut along road and asphalt parking, and replace with curb and gutter. Am I figuring cutting out a wide strip or just a single pass?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

6.) There is a concrete pad and sidewalk in the front left corner of the building, is this to be removed?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

7.) Is the chain link fence behind the building on the concrete slab to be removed?

RESPONSE: SEE NOTE IN EMAIL ABOVE.

A1:

1.) Is there a more detailed drawing of this sheet and what is to be removed?

RESPONSE: IF THE ITEM IS SHOWN ON THE EXISTING PLAN AND NOT ON THE RENOVATED PLAN IT IS TO BE REMOVED. IF THE ITEM IS SHOWN ON THE EXISTING AND RENOVATED PLANS IT IS TO REMAIN.

2.) There are water lines showing to be removed that run across Co. Street F, what are the extent of the removal of these lines? Are we required to remove these? Are we pulling up the road to access these lines if needed?

RESPONSE: SHEET A1 SHOWS THE REMOVAL OF WATER LINES CROSSING CO. STREET F AND THE ASPHALT PATCHED. THESE LINES FED BUILDINGS THAT HAVE BEEN REMOVED. ASSUME THE WATER LINE EXTENDS 25' TO THE SOUTH FROM THE EDGE OF THE STREET PAVEMENT AT EACH LOCATION.

3.) The telephone lines and boxes are to be removed judging by the drawings, but will be located later after awarding of the contract, are we pricing just removal of the boxes?

RESPONSE: FOR THE PURPOSE OF BIDDING ASSUME TO REMOVE 100' OF PHONE LINE.

