

CONTRACT # N00485-12-B-0411
PROJECT # 12R031CN
MACC # 12-0411
MAXIMO# 4394292

TITLE: FRENCH CREEK CROSSWALKS

ATTACHMENTS:

1) Site Plan, 1 Page

SCOPE OF WORK (2 Pages)

The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

General description – The contractor shall:

Install six new thermoplastic crosswalks as directed in this scope of work and as shown in the attached site plan. Signage is not included as part of this project. Signs shall be installed by the base contractor that handles the signage for Camp Lejeune once crosswalks are in place.

The P.O.C.'s have no authority to alter this scope of work.

All work related issues must be coordinated with the government project manager.

Detailed requirements and specifications – The contractor shall:

- Install 6 crosswalks using REFLECTIVE PRE-FORMED THERMOPLASTIC TAPE, installed/applied to the manufacturers' specifications to provide a neat and clean appearance. Reflective characteristics shall meet or exceed N.C.D.O.T. specifications according to the N.C.D.O.T. STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES as they apply to crosswalks.
- The six crosswalk locations are listed below.

1) Located crossing Gonzales Blvd. and centered on the middle sidewalk in front of Bldg. FC560. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

2) Located crossing Gonzales Blvd. and centered on the middle sidewalk in front of Bldg. FC555. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

3) Located crossing Gonzales Blvd. and centered on the middle sidewalk in front of Bldg. FC550. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

4) Located crossing Gonzales Blvd. and centered on the middle sidewalk in front of Bldg. FC530. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

5) Located crossing Reasoner St. and centered on the middle sidewalk in front of Bldg. FC525. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

6) Located crossing Reasoner St. and centered on the middle sidewalk in front of Bldg. FC520. The middle sidewalk is the one that comes from the center of the bldg.

- Install one N.C.D.O.T. compliant “High Visibility” crosswalk.

SPECIAL SCHEDULING AND ACCESS:

The contractor shall provide traffic control (i.e. cones, flagman, signs, etc.) sufficient to prevent injury to personnel, damage to property, and allow for safe flow of traffic. Notify the Base Provost Marshall’s Office (PMO), 451-3004/3005, prior to detouring or re-routing traffic.

SPECIAL CONDITIONS:

None.

POINTS OF CONTACT:

Kurt Rasenberger, Operations Branch, (910) 545-9251 kurt.rasenberger@usmc.mil

Charles Wood, Base Safety, (910) 467-7532 charles.dwood@usmc.mil